ADDENDUM No. THREE (3) TO PROJECT DOCUMENTS ITB#7-2016/2017 Gulf Coast State College PHASE 2 CAMPUS IMPROVEMENTS PROJECT FLA Project No. 4166-14 June 5, 2017



ADDENDUM NO. THREE (3)

The Construction Drawings and/or Project Manual for the above project are amended in the following particulars and in these particulars only. All provisions of the original drawings and/or specifications shall remain in force, except as specifically modified or changed herein or by other Addenda issued by the Architect. This Addendum is hereby made part of the Contract Documents.

This Addendum incorporates responses to questions received to date.

PROJECT MANUAL/SPECIFICATIONS (PM):

None.

DRAWINGS:

None.

OTHER QUESTIONS AND RESPONSES:

Q1: Is it possible to get details on where the Type D Curb is located? Nothing is shown in plan

set.

Response: There is no D curb in phase II. We were using D curb around the landscape median islands

that were removed during the design review process. We did not remove the detail.

Q2: Is 6" LRB required under all curb as shown in the Landscape Island Typical Section for the

Type D Curb on sheet D1? If so, please add to curb details.

Response: The Base is not required under the D curb, but we will require stabilized subgrade to extend

underneath the curb.

Q3: Subgrade extents beyond curb pad requirements?

Response: The Base is not required under the curb, but we will require stabilized subgrade to extend

underneath the curb.

Q4: Sheet D1 shows a Typical Section for Asphalt Overlay. Please identify where Overlay is

proposed.

Response: There is no asphalt overlay areas within phase II. Please disregard detail.

End of Addendum No. 3